

KATHMANDU UNIVERSITY SCHOOL OF MEDICAL SCIENCES

Dhulikhel, Kavre

Bill of Quantities

FOR

Repair and maintenance of CGI Sheet roofing in Academic Block/ Lab Block

Choukot

S.No	Particulars	Quantity	Units	Rate		Amount	Remarks
				In figure	In words		
1.00	Dismantalling of old CGI Sheet roofing and Gutter including removing off of debris in appropriate place, stacking of CGI Sheet and gutter, scaffolding, all complete as per instruction.	1026.840	Sq.m				
2.00	Supply and installation of 26 gauge red coloured C.G.I sheet roofing including hooks, clamps, scaffolding, etc. all necessary item all complete as per instruction.	1026.840	Sq.m				
3.00	Supply & fabrication of red coloured G.I Plain sheet gutter including hooks, clamps, nails, scaffolding, etc all necessary item all complete as per instruction.	153.720	Rm				
4.00	Supply and fabrication of red coloured GI plain sheet ridge including hooks, clamps, nails, scaffolding, etc all necessary item all complete as per instruction.	60.790	Rm				
5.00	Supply and installation of 4" dia PVC pipe including all required fittings for Gutter as per instruction.	90.000	Sq.m				
6.00	Dismantalling of existing false ceiling including removing off of debris in appropriate place, scaffolding, etc. all complete as per instruction.	609.420	Sq.m				
7.00	Supply & fixing of Silver Laminated Smart Gypsum board false ceiling of size 600x600 mm with all necessary ss strip, hanger, angles, hooks, nut bolt, scaffolding, etc. all complete as per instruction.	609.420	Sq.m				
8.00	Applying two coats of enamel painting over primer on cleaned surface of steel or metal, all complete the work as detailed in drawing, specification and instructions of the Engineer.	1.000	Job				
				Sub Total			
				VAT - 13.0 %			
	Total Amount (including VAT - 13%) NRS :-						

971