

DHULIKHEL HOSPITAL- KATHMANDU UNIVERSITY HOSPITAL
DHULIKHEL, KAVRE, NEPAL

SUMMARY OF BOQ
FOR
Repair and maintenance of Hostel Buildings

S.No.	Description	Amount	Remarks
A	Holland Hostel		
B	Japanese Hostel		
C	Luxemberg Hostel		
	Sub Total		
	VAT -13.0%		
	Total (including VAT- 13.0%)		



DHULIKHEL HOSPITAL- KATHMANDU UNIVERSITY HOSPITAL
DHULIKHEL, KAVRE, NEPAL

BOQ
FOR
Repair and maintenance of Holland Hostel Buildings

S.N	DESCRIPTION	UNIT	QUANTITY	RATE (NRs.)		AMOUNT	REMARKS
				In Figure	In word		
A	Holland hostel						
1	Supply and fixing of S.S. mosquito net only with required accessories as per instruction all complete.	Sq.m	2.24				
2	Supply and installation of Sliding wiondow lock as per instruction.	No.	4.00				
3	Removing of old door net and Replacement of door net as per instruction all complete.	Sq.m	1.89				
4	Supply and installation of mortice lock as per instruction.	No.	17.00				
5	Supply and installation of bathroom mirror (450x600 mm) as per instruction.	No.	4.00				
6	Supply and installation M.S Grill with one coat of red oxide and two coat of Enamel paint as per instruction all complete.	k.g	704.16				
7	Supply and installation of chain gate one coat of red oxide and two coat of Enamel paint , etc. all complete as per instruction.	Sq.m	7.59				
	Sub-Total						



DHULIKHEL HOSPITAL- KATHMANDU UNIVERSITY HOSPITAL
DHULIKHEL, KAVRE, NEPAL

BOQ
FOR
Repair and maintenance of Japanese Hostel Buildings

S.N	DESCRIPTION	UNIT	QUANTITY	In figure	RATE In Word	AMOUNT	REMARKS
B	Japanese hostel						
1	Supplying and fixing of Natural colour Aluminium casement/sliding door with loover/ventilator works (101 series) with sections of different size including 5mm thick glass panes, Aluminium panel at bottom as per requirement of approved quality including gaskets, screws and Aluminium strips, tower bolt, Mortice locks, handle, 4 No. of high quality S.S. hinge, door stopper and closer, are must etc., all complete as per design, drawing, specification and instructions.	Sq.m	3.36				
2	Supply and fixing of S.S. mosquito net only required accessories as per instruction all complete.	Sq.m	5.04				
3	Supply and installation of Sliding window lock as per instruction.	No.	20.00				
4	supply and installation of Gasket as per instruction (1 Roll =5k.g)	Roll	2.00				
5	Supply and installation of mortice lock as per instruction.	No.	28.00				
7	Supply and installation of bathroom mirror (450x600mm)as per instruction.	No.	4.00				
8	Supply and installation of commode spray (jaquar company)as per instruction.	No.	5.00				
9	Plain cement concrete works in 1:2:4 for Step in front of hostel with OPC cement in perfect line and level including curing, centering & shuttering of form work, etc. as per design, drawing, specification and instructions.	Cu.m	0.13				



DHULIKHEL HOSPITAL- KATHMANDU UNIVERSITY HOSPITAL
DHULIKHEL, KAVRE, NEPAL

**BOQ
FOR**

Repair and maintenance of Japanese Hostel Buildings

S.N	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT	REMARKS
10	Supplying and laying of Flag stone pavement in 1:4 cement sand mortar as per instruction.	Sq.m	1.49			
11	Supply and installation M.S Grill with one coat of red oxide and two coat of Enamel paint as per instruction all complete.	k.g	1,061.91			
12	Supply and installation of chain gate one coat of red oxide and two coat of Enamel paint , etc. all complete as per instruction.	Sq.m	11.97			
				Sub-Total		



DHULIKHEL HOSPITAL- KATHMANDU UNIVERSITY HOSPITAL
DHULIKHEL, KAVRE, NEPAL

**BOQ
FOR**

Repair and maintenance of Luxemberg Hostel Buildings

S.N	DESCRIPTION	UNIT	QUANTITY	In Figure	RATE (NRs.) In Word	AMOUNT	REMARKS
C.	Luxemberg Hostel						
1	Dismantling of floor tile, flagstone, level concrete, P.C.C., etc including removal of debris in appropriate place as per instruction.	Cu.m	3.65				
2	Earthwork in excavation for pipe maintenance and laying of pipe as per instruction.	Cu.m	0.90				
3	Backfilling to structures, foundations pits, floor, side drains, etc. from excavated materials including compaction, all complete as per drawing and instruction of the Engineer.	Cu.m	0.85				
4	Flat brick soling in wall in perfect line and level including blinding the joints with sand as per design, drawing, specification and instructions	Sq.m	24.00				
5	Plain cement concrete works in 1:2:4 for drain and pavement with OPC cement in perfect line and level including curing, centering & shuttering of form work, etc. as per design, drawing, specification and instructions.	Cu.m	2.51				
6	Supplying and laying of Flag stone pavement in 1:4 cement sand mortar as per instruction.	Sq.m	24.00				
7	Supply and installation of 4" dia PVC pipe including required fitting accessories all complete as per instruction.	Rm	5.00				



[Handwritten signature]

DHULIKHEL HOSPITAL- KATHMANDU UNIVERSITY HOSPITAL
DHULIKHEL, KAVRE, NEPAL

BOQ
FOR
Repair and maintenance of Luxemberg Hostel Buildings

S.N	DESCRIPTION	UNIT	QUANTITY	In Figure	RATE (NRs.) In Word	AMOUNT	REMARKS
C.	Luxemberg Hostel						
8	Internal wall Plaster: 12.5 to 20mm thick cement plaster in (1:4) cement sand mortar on wall and concrete surface (internal surfaces) in perfect line and level including cleaning, chipping, cutting and raking the joints curing till 7 days, etc. all complete as per design, drawing, specification and instructions .Note: Sand Should be washing sand.	Sq.m	4.50				
9	Supply and installation of Sliding window lock as per instruction.	No.	8.00				
10	Supply and fixing of S.S. mosquito net only required accessories as per instruction all complete.	Sq.m	4.50				
11	Applying two coats of Emulsion painting of Asian paints or equivalent paint of approved quality over a coat of primer on some internal surfaces.	Sq.m	40.08				
12	Supplying and laying out Non-glazed ceramic tiles on toilet floor of 300X300mm size in floor and glazed ceramic wall tiles of 300X450mm size in wall SOMANY or equivalent approval quality tiles in perfect line level by using water based adhesive chemical of required thickness, colour pigment if required and cleaning, tile grout material should be epoxy based, etc, all complete as per design, drawing, specification and instruction. Note: the rate shall include all required base preparation upto 125mm	Sq.m	25.73				



BOQ
FOR

Repair and maintenance of Luxembourg Hostel Buildings

S.N	DESCRIPTION	UNIT	QUANTITY	In Figure	RATE (NRs.) In Word	AMOUNT	REMARKS
C.	Luxemberg Hostel						
13	Supply and apply PP Membrane of 0.8mm thick for water proofing works in open terrace, toilet floor & wall , maintaining the overlapping of minimum of 10cm all complete as per drawing, specification, and instruction of Engineer .Note : the contractor sholud provide warrentee of minimum 10 years.	Sq.m	25.73				
14	Supply and installation of mortice lock as per instruction.	No.	17.00				
15	supply and apply of Silicon as per instruction all complete.	Cane	3.00				
16	Supply and installation of bathroom mirror (450x600mm)as per instruction.	No.	4.00				
17	Supply and installation M.S Grill with one coat of red oxide and two coat of Enamel paint k.g	k-g	937.30				
18	Supply and installation of chain gate one coat of red oxide and two coat of Enamel paint , Sq.m	Sq.m	8.04				
				Sub-Total			

